Sectt. II-27—36,006—30-10-37.

P.W. (193 8) Department

M8 SERIES.

G.O. No. 202

DATED 2 2 1938

[Despatch Abstract.]

C.F. 30.

Education and Public Health DEPARTMENT.

25366

Received ..... 19 *Registered* 19

23 DEC 1937

Subject.

Buildings.

Govt., Headquarters Hospital, Bellary - Improvements to the Nurses quarters at - Estimate Rs.3400/-.

ENCLOSURES.
No. .....
.....
Spare copies .....

Ref. No. 670-Genl./36.

Station **Madras.**, *Dated the* 22nd Dec. 1937. 19

From (Name) **Colonel N.M. Wilson, O.B.E., I.M.S.,**

(Designation) **Surgeon-General with the Government of Madras.**

To The Secretary to the Government of Madras,

Education and Public Health Department.

Sir,

I have the honour to forward for the administrative approval of Govt., plans and an estimate amounting to Rs.3400/- for improvements to the nurses quarters at the Govt., Head-quarters Hospital, Bellary. The necessity for the work is explained in the report accompanying the estimate. A sum of Rs.1000/- has been provided in the current year and balance will be provided during 1938-39. A rent data statement is also enclosed herewith.

I have the honour to be
Sir,
Your most obedient servant,

22-12-37

Personal Assistant.
For Surgeon-General with the Govt., of Madras.

REPORT TO ACCOMPANY THE ESTIMATE FOR IMPROVEMENTS TO THE NURSES QUARTERS AT THE HEADQUARTERS HOSPITAL, BELLARY.

ESTIMATE AMOUNT Rs. 3400/-

Item No. 117A in the Register of buildings, Bellary Dist.,

This estimate has been prepared as per requisition from the District Medical Officer, Bellary in his No. 102/37 dated 25-1-37.

There are at present 6 Nurses working in the Hospital, while there is accommodation only for four. For want of adequate accommodation, the two nurses are at present occupying the Quarters for the Junior Sub Asst. Surgeon

This estimate therefore provides for the construction of two bed rooms with 2 bath rooms in the first floor of the Western half or the building (Nurses Quarters) to accommodate the two nurses.

WALLS. The walls will be of burnt stone in lime mortar 1:2 and 1'-6" thick.

FLOOR.- The existing plaster will be scraped up and the floor levelled and plastered with cement mortar ½" thick 1:3.

WOOD-WORK.- All roof timbers shall be of best teakwood.

ROOF.- The roof will be of Terraced roofing with 2" Cuddapah slabs, 4" broken stone jelly concrete ¾" guage in lime mortar 1:2, 2 courses of flat tiles set in cement mortar 1:4 mixed with crude oil and plastered over with lime mortar 2 coats and bottom white-washed.

FINISHING.- All inside will be plastered with lime mortar 2 coats and outside pointed with cement mortar 1:3. The verandah opening will be fixed with hand rails 2'-9" nigh. The existig ladder stair case, will be fixed in a suitable place, for getting to the I floor. All timbers will be painted with 3 coats of grey or slate colour paint. Reinforced concrete lintels will be provided over openings and door and windows.

Executive Engineer,

Bellary Division.

SSS.3/10.

25/5/37

Statement giving data for calculating rent of Government

Item No.	Name of building.	Official designation and salary of occupant.	Permanent or temporary.	Date of construction or purchase.	Capital cost.			6½ per cent on capital cost for interest.
					Cost of construction or purchase.	Cost of site.	Total.	
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
					Rs.	Rs.	Rs. (a)	Rs.
117	Quarters for three Nurses		P	1929	11427	-	11427	
	Nurses Head qrs Rs 60 to 90						(b)	
(1)	Hospital Bellary Addl of Electric installation				160		160	
(2)	Add Cost Rs. additional Electric installation as per Est Rs 200 of Electrical Engineer Regr No 564 Rs. 36-37				182		182	
(4)	Add Cost Rs. improvements now proposed as per estimate herewith enclosed				3400		3400	
(3)	Add Cost Rs. improvements to end of September 37 as per estimate for Rs 1694 TOR 93 Rs. 36-37 (Work not yet Completed)				1510		1560	
					16729		16729	1004

Buildings in the **Division.** 1605/13

Cost of maintenance and repairs.			Normal rate of rent on basis of foregoing calculation.		Rent hitherto charged.	Remarks.
Ordinary repairs.	Special repairs at per cent.	Total.	Annual, columns 9+12.	Monthly, $\frac{1}{12}$ of column 13.		
(10)	(11)	(12)	(13)	(14)	(15)	(16)
Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	

(a) Bore Register of Buildings of Bellary Dist item 117 A

(b) As estimated by the Electrician Bellary

(c) This rate will have effect from date of Completion ~~and~~ of the improvements proposed.

D.F.O. Nellore

E.E.

ML 1-10-37.

✓ (c) Q

1004 838/12 Rentree 21/10/37

Rs 84/- ✓

4

E.&.P.H. Dept.

Buildings - Headquarters Hospital, Bellary -
Improvements to the quarters of nurses.

C.F C.No. 25666-From the S.G., No. 670-G., d. 22-12-'37.

The S.G. has submitted an estimate amounting to Rs. 3,400/- for providing accommodation for two more nurses in the existing nurses quarters attached to the Headquarters Hospital, Bellary. It is statedxkk that at present there is accommodation for only 4 nurses, while there are actually six nurses employed in the nospital. Two nurses are now reported to be ~~employed~~ occupying ~~in~~ the quarters intended for the ~~senior~~ Junior S.A.S. In the circumstances, the necessity for additional accommodation for the nurses may be ~~accepted~~ conceded and the file may be passed on to P.W.D. U.O. for issuing orders.

3.1.38.

4/1/38

P.W.D.

C.No. 25666 A 52
7.1.38.

C160

P.W.D.

A draft order is submitted. It may be sent to Finance for acceptance

24/1/38
Sm
24/1

lcl
24/1

Hkm
25/1

7 D

P.W. ms No. 1606/38.1
26.1.38

Finance E.I.

The draft order may be accepted and the case returned to the P.W.D. w.o.

27.1.38.

Hy
28.1.38

D.S.

Ckd/29.1.38

P.W.D.

Issue
lcl
31/1

ASST. SECRETARY TO GOVT.
C
31 JAN 1938
492
PUBLIC WORKS DEPT.

Finance 3243 EI-1
29.1.38

24/2/38

DRAFT FOR APPROVAL.

6

C.F. 16. P.W.D.

	Date.	Initials.
When received for fair copying ..		
When copied ..		
When examined..	24/2	
When signed ..		
When despatched.		

SUBJECT:—

Buildings - Bellary. Headquarters hospital - construction of 2 additional rooms for nurses' quarters - Expenditure Rs 3400/- Approved.

READ AGAIN _____, dated _____ 19____.

" " _____ " _____ 19____.

READ *ALSO*:—

No. 1600 From the S.E. , No 670 Ge/36, dated 22.12.1937.

" _____ " _____ " _____ " _____ 19____.

" _____ " _____ " _____ " _____ 19____.

Order ~~Resolution~~ Ms. ~~Rout.~~ No. 202, dated 2-2-1938.

Govt. approve an expenditure of Rs 3400/- (Rupees three thousand and four hundred only) for the provision of two additional rooms with bath rooms for nurses at the headquarters hospital Bellary.

The expenditure may be met from the lump sum provision for minor works in the budget under "SD a Civil Works - Original works - Buildings - Medical".

22/1/38

Sec.I

24/1

Deft. Secy. 31/1/38

To the CE (General) with plans & estimate

S.E. thro' E.P.W. Deptt.